

PARCEL / PROPERTY LINES, SETBACKS, PARKING, UTILITIES, STORMWATER: TBD (D-006)

N

S1 SERVICE / LOADING (D-034)

X3

X3

X2

X1

X10

X4

X5

NE TOWER 21.33' x 6.67'

ST-2

X7

X8

ST-3

X9

PORTAL

(freestanding, 50' max)

drop curb

extend to
parking later

offset E (or W) of the
portal view (D-034);
diagram — size TBD

ROAD (assumed south; site TBD, D-006)

2 ENTRY — PORTAL + CHAMPION WALK — 1" = 30'

BUILDING (south wall)

30'

28'

LEGEND

- Building, P2-A-101 Rev E (210' + NE tower)
- Superseded Rev D outline (dashed)
- Exit stairs 76" clear (D-052)
- Event floor
- Champion Walk (brick)
- Portal piers (limestone)
- Service drive / apron (diagram)
- Bus drop loop (diagram)
- Road (assumed)
- E1 main entry / S1 service door

SIZE — D-057 (no cap, no margin; D-056)

	DRAWN Rev E	REV D drawn	CHANGE	PROGRAM G	DRAWN — PROG.
L1 FOOTPRINT	53,062.2	51,503.0	+1,559.2	54,240.9	−1,178.7
L2 AREA	28,914.2	28,363.0	+551.2	28,012.1	+902.1
TOTAL GSF	81,976.5	79,866.0	+2,110.5	82,253.0	−276.6

Drawn = P2-A-101/102 Rev E (L2 = L1 minus open-to-below). Program = P2-G-003 Rev G: footprint (max of L1 gross, arena volume + L2) + L2 gross; L1 + L2 gross = 80,747.5. C-101 Rev A showed L1 53,026.7 with a 5' tower; Rev E draws the tower 6.67' deep: +35.5 SF. Size is set by budget and parcel (D-012, D-006).

STATUS

- SITE TBD (D-006): this is a layout diagram, not a site plan for permit. Parcel, property lines, setbacks, grading, parking count, utilities and stormwater are TBD. AHJ (R-006): Madison County Inspection Department if the parcel is unincorporated (Hazel Green is); the county states no zoning limits on construction; county codes 2018 IBC / IFC / NFPA 101; State Fire Marshal 2021 IFC.

ENTRY (DECIDED)

- Freestanding limestone portal over the walk (D-043), 50' max (D-050), 44' wide x 6' deep (ASSUMED), 30' south of the E1 doors (D-046). Champion Walk 28' x 30' = 840 SF brick, ≈ 3,700 4x8 donor bricks; vendor cost ≈ \$70.9k if all 4x8 (Shane's sheet, D-044 input; install + base not included). Dashed: later extension to parking.

BUS + SERVICE (D-034 DECIDED defaults)

- South bus drop loop offset EAST so it does not block the portal view (west is equally allowed; the SW FLEX / team assembly room would favor west). Drop curb links to the walk's south end. Service / deliveries at the north door S1 by a west-side drive (alignment TBD). Loop, drive and apron are diagrams: lane widths, bus turning template and apron size TBD (civil).

BUILDING (AS DRAWN ON P2-A-101 / A-102 REV E)

- 210' x 252': east seats 16' from the mats (D-053); exits X6-X9 on the new east wall. NE stair tower 21.33' x 6.67' = 142.2 SF (the 76" ST-2 sits north of the loop's north leg; Rev A showed 5'). Stairs ST-1..ST-4 76" clear, 12.67' x 21.33' (D-052, D-051).
- Upper tier 19" risers; 6' low band under its front (D-049). Exit paths under the band: D-061 OPEN (R-022). Option B (raise L2 to 17'-9") would lengthen each stair ≈ 2.75' (NE tower ≈ 9.4' deep).

FIRE ACCESS / WATER (TBD)

- Fire apparatus access roads, hydrants and fire flow per IFC Appendices B, C, D (State Fire Marshal, 2021 IFC; D107 recommended) and the county's 2018 IFC. Exit discharge from X1-X10 to a public way (IBC 1028) TBD with the parcel.

1 SITE PLAN — CAMPUS DIAGRAM (SITE TBD)

1" = 60'-0" · north approximate · road assumed south · diagram only (no surveyed dimensions)



PRELIMINARY — CONCEPTUAL DESIGN — NOT FOR CONSTRUCTION

PROJECT

Hazel Green Regional Athletic Complex
Trojan Horse Arena · Hazel Green area, Madison
County, Alabama (site TBD, D-006)

PHASE

PHASE 2

SHEET TITLE

SITE PLAN — CAMPUS DIAGRAM
SITE TBD · SCHEMATIC

SCALE

AS
NOTED

DATE

October
2026

REV

B

DRAWN BY

Drawn by KEYSTONE (AI) for
Shane Brazelton

SHEET

P2-C-101