

SCHEMATIC — BLOCK PLAN, CONCEPT ENVELOPE

LEVEL 2 — OVERALL FLOOR PLAN (REV I)

Rev H with the drum at 30 ft (D-082) and the drum door slid west along the arc (D-083). Rooms, tiers, guards, seats, loop and the R 13 NE loop corner as Rev H. Rev H 29 ft drum dashed. Level 2 is the same in plan Rev I and Rev J.

CHANGES FROM REV H (all ASSUMED unless cited)

- ST-2: 30 ft drum, same centre; south edge y 247.5 (1.5 ft clear of the loop). Stair fit 1.49 ft spare (Rev H 0.49). +35 SF on this level.
- Drum door slides west from 240° to 235° (centre 173.4, 250.2): the most westerly point that keeps the 64 in pair inside the north wall (west jamb y 251.94). Door swings into the drum (direction of egress), so the loop width is not reduced.
- Landing (IBC 2021 1010.1.5: width >= 76 in stair, length >= 44 in): door centre to loop edge along the door line 61.7 in (Rev H 54.6). The full 76 x 44 in landing (dashed) reaches 4.9 in onto the loop's outer edge at one corner.

ROOM SCHEDULE — LEVEL 2 (SF net of stairs, inside the envelope)

TAG	ROOM	REV H	REV I	CHANGE
—	Upper tier, fixed (1,100 seats)	6,930	6,930	0
17	Strength & Conditioning	5,038	5,038	0
18	Cross-Training Mat	3,500	3,500	0
19	Men	550	550	0
20	Women	900	900	0
21	Admin	470	470	0
—	L2 Corridor	2,192	2,192	0
—	Upper Concourse (E)	994	994	0
—	Stretch / Warm-up (N)	708	708	0
—	ST-2 landing / NE corner (not programmed)	142	131	-11
—	Running / training loop	5,006	5,006	0


AREA CHECK (no SF cap, D-056; L1, L2, total vs last rev, D-057)

	REV L / H	REV M / I	CHANGE
L1 footprint (P2-A-101 Rev M)	57,861	57,896	+35
L2 area (envelope - open-to-below)	29,033	29,068	+35
TOTAL GSF	86,894	86,964	+70

L2 = envelope 53,216 SF - open-to-below 24,148 SF (arena 132 x 168 + lobby 58 x 34), the Rev F / G method. Rev L / H baseline = P2-G-003 Rev L. Carried to P2-G-003 Rev M.

OPEN (not decided here)

- Landing reaches 4.9 in onto the outer loop lane at one corner (strip alone at the east jamb: 35 in). Architect: count that corner of the corridor as landing (door swings away from it), or not. See P2-G-003 Rev M.
- Drum floor-to-floor, wall and roof; structure of the curved shell; tier depth 1'-6" or less (D-061).
- SRM / Summertown Metals roles are not agreed; names are descriptive, no marks used (D-042).



Sources: params/phase2_plan_rev_j.yaml (L2 as Rev F); phase2_plan_rev_k.yaml; phase2_plan_rev_g_l2.yaml; phase2_plan_rev_m.yaml; IBC 2021 1010.1.5; D-079..D-084.

PRELIMINARY — CONCEPTUAL DESIGN — NOT FOR CONSTRUCTION

PROJECT	PHASE	SHEET TITLE	SCALE	DATE	REV	DRAWN BY	SHEET
Hazel Green Regional Athletic Complex Trojan Horse Arena · Hazel Green area, Madison County, Alabama (site TBD, D-006)	PHASE 2	OVERALL FLOOR PLAN LEVEL 2 · BLOCK PLAN	1" = 40'-0"	October 2026	I	Drawn by KEYSTONE (AI) for Shane Brazelton	P2-A-102