

PROGRAM + AREA — REV M · P2-A-101 REV M / A-102 REV I · 30 FT DRUM, DRUM DOOR, EAST SIDE = PLAN REV J

Program lines unchanged from P2-G-003 Rev K (frozen, Set Rev D). Drawn size (D-057) measured on P2-A-101 Rev M / A-102 Rev I. No SF cap (D-056). Planning only: architect confirms.

1 SIZE — D-057: L1 FOOTPRINT · L2 AREA · TOTAL GSF · CHANGE

	SET REV D	REV L / H	REV M / I	vs L / H	vs SET REV D
L1 FOOTPRINT	56,861	57,861	57,896	+35	+1,035
L2 AREA	28,933	29,033	29,068	+35	+135
TOTAL GSF	85,793	86,894	86,964	+70	+1,171

Drawn on: SET REV D = P2-G-003 Rev K (A-101 J / A-102 F); REV L / H = P2-G-003 Rev L (29 ft drum, D-081); REV M / I = this sheet. Totals are the sum of the rounded levels.

Why +70 vs Rev L / H: the drum grows from 29 to 30 ft on both levels (+35 each). The east side moves back to plan Rev J (D-084) with the same bump-out size (1,680 SF), so L1 does not change from it.

2 HOW L1 AND L2 ARE MEASURED (Rev G method, D-079)

- Envelope = 210 x 252 ft box with R = 20 ft corners (D-077) united with the 30 ft drum at (182, 262.5): 53,216 SF.
- L1 = envelope + storage annex 2,100 + mech / elec bay 900 (x 134-164) + restroom bump-out 1,680 (y 119-175) = 57,896.
- L2 = envelope - open-to-below 24,148 (arena 132 x 168 + lobby 58 x 34) = 29,068.

3 PROGRAM (carried from P2-G-003 Rev K; no program line changes)

PROGRAM LINE (G-003 K)	SF	DRAWN REV M	DRAWN - PROG.
L1 gross incl. annex + bump-out	56,713		
L2 gross (rooms x 1.25 + loop)	28,186		
L1 + L2 gross	84,899		
Program footprint (max + annex + bump-out) vs L1	58,195	57,896	-299
PROGRAM TOTAL GSF vs drawn TOTAL	86,381	86,964	+583

The drum, the R = 20 ft envelope and the bay are circulation / building form, not program lines; the stair line (4 x 76 in, 31 risers, 12.67 x 24.08 ft each) is unchanged. Mech total about 4.1 % vs 5 % stays OPEN (D-072).

4 ROOMS THAT CHANGE vs REV L / H (SF net of stairs)

LEVEL / ROOM	REV L / H	REV M / I	CHANGE
L1 15 MECH (N)	571	564	-8
L1 16 MECH (E)	1,720	675	-1,045
L1 25 MEN (2)	0	364	+364
L1 26 WOMEN (2)	0	1,020	+1,020
L1 27 DF / JAN.	0	56	+56
L1 28 MECH (E2)	0	660	+660
L1 25-27 Restroom pop-out block (Rev L)	1,680	0	-1,680
L2 ST-2 landing / NE corner (not programmed)	142	131	-11
L1 + L2 ST-2 drum (29 -> 30 ft, each level)	660	707	+46

5 STAIR FIT · DRUM DOOR LANDING (D-082, D-083)

- Stair fit: 12.67 x 24.08 ft stair, diagonal 27.21 ft in 28.7 ft inside (30 ft less 1.3 ft walls, ASSUMED): 1.49 ft spare, about 9 in at each end corner (Rev L 0.49 ft).
- Door: 64 in pair at 235° (Rev H 240°), centre (173.4, 250.2), swings into the drum. 235° is the most westerly point that keeps both jambs inside the north wall.
- Rule, IBC 2021 1010.1.5 (1010.1.6 in IBC 2018): landing width not less than the stair or door width, whichever is greater (76 in), length in the direction of travel at least 44 in; door swing may reduce it by no more than 7 in.
- Clearance: door centre to the loop edge along the door line 61.7 in (Rev H 54.6) vs 44 in. The 76 x 44 in rectangle square to the door reaches 4.9 in onto the loop's outer edge at one corner; the strip alone at the east jamb is 34.5 in.

6 EXITS / TRAVEL / COMMON PATH RECHECK (east side = plan Rev J, D-084)

- PASS (as calculated) T1 event floor -> X7: 133 ft vs 250 (Set Rev D 133).
- PASS (as calculated) Women (2) common path 61 ft (to X11 78); men (2) 30 ft (to X11 43); limit 75 (Set Rev D 61 / 30).
- PASS (as calculated) Public corridor (E) 96 in vs 44; inside the envelope; dead end 5.2 ft vs 20.
- PASS (as calculated) X7 (y 179.09), X11 (y 112), X8 (y 34) on the straight east wall, clear of the bump-out; X7 jamb 1.33 ft north of it.
- PASS (as calculated) L2 travel, worst point (206, 140): about 160 ft incl. 15 ft seat access. Stair separation 141 ft vs 1/3 diagonal 109 ft.
- PASS (as calculated) X6 on the drum east face (197.0, 262.5), clear of annex and bay; drum to bay 3.0 ft; X5 lane 12 ft.

7 FINDINGS + OPTIONS (not redesigned here)

F1 Drum door landing: a 76 x 44 in landing square to the door reaches 4.9 in onto the loop at one corner. Options: (a) architect counts that corridor corner as landing (door swings away from it); (b) widen the strip locally at the drum; (c) smaller door leaf (not checked vs capacity).

F2 X7 / X11 discharge to the public way is TBD (D-006, site not chosen); not checked here.

F3 The old NE stair strip inside the box (about 67 SF on L1) stays unassigned.

F4 Mech total about 4.1 % vs 5 % stays OPEN (D-072). Drum structure / roof not drawn.

8 SOURCES

D-057, D-072, D-077..D-084 (DECISIONS_ARENA); params/phase2_plan_rev_j.yaml (= Set Rev D A-101 J), _rev_k, _rev_g_l2, _rev_l, _rev_m; phase2_life_safety_rev_d.yaml / phase2_code_rev_d.yaml (handoff, read only); IBC 2021 1010.1.5, T1017.2, T1006.2.1, 1020.5, T1020.3. Revs A-L of P2-G-003 unchanged.

PRELIMINARY — CONCEPTUAL DESIGN — NOT FOR CONSTRUCTION

PROJECT	PHASE	SHEET TITLE	SCALE	DATE	REV	DRAWN BY	SHEET
Hazel Green Regional Athletic Complex Trojan Horse Arena · Hazel Green area, Madison County, Alabama (site TBD, D-006)	PHASE 2	PROGRAM + AREA D-082 · D-083 · D-084	NTS	October 2026	M	Drawn by KEYSTONE (AI) for Shane Brazelton	P2-G-003