

PROGRAM + AREA — REV L · P2-A-101 REV L / A-102 REV H · NE STAIR DRUM (D-081)

Program lines unchanged from P2-G-003 Rev K (frozen, Set Rev D). Drawn size (D-057) measured on P2-A-101 Rev L / A-102 Rev H. No SF cap (D-056). Planning only: architect confirms.

1 SIZE — D-057: L1 FOOTPRINT · L2 AREA · TOTAL GSF · CHANGE vs LAST REV

	G-003 K	REV K / G	REV L / H	vs K / G	vs G-003 K
L1 FOOTPRINT	56,861	57,520	57,861	+341	+1,000
L2 AREA	28,933	28,692	29,033	+341	+100
TOTAL GSF	85,793	86,212	86,894	+682	+1,101

Drawn on: G-003 K = A-101 J / A-102 F (Set Rev D); REV K / G = A-101 K / A-102 G as corrected on A-102 G (D-079); REV L / H = this ticket. Change vs last rev = vs REV K / G.

2 THE NUMBER YOU EXPECTED vs THE NUMBER COMPUTED

Expected: +682 -> 86,475 GSF. Computed: +682 -> 86,894 GSF. The +682 matches; the base does not. 86,475 = 85,793 (Set Rev D) + 682, which leaves out the +418 of the R = 20 ft envelope, tower and bay on Rev K / G (D-079: 86,212). From Set Rev D the drum ticket and Rev K / G together add +1,101 SF (85,793 -> 86,894).

Rounding: G-003 K prints 85,793; A-101 K / A-102 G use 85,794 for the same Rev J plan (56,861 + 28,933 each rounded).

3 HOW L1 AND L2 ARE MEASURED (Rev G method, D-079)

- Envelope = 210 x 252 ft box with R = 20 ft corners (D-077) united with the 29 ft drum at (182, 262.5): 53,181 SF (Rev K / G: 52,840 with the 20 ft tower).
- L1 = envelope + storage annex 2,100 + mech / elec bay 900 (x 134-164) + restroom bump-out 1,680 = 57,861.
- L2 = envelope - open-to-below 24,148 (arena 132 x 168 + lobby 58 x 34) = 29,033. The drum counts on both levels, so each level gains 341 SF.

4 PROGRAM (carried from P2-G-003 Rev K; no program line changes)

PROGRAM LINE (G-003 K)	SF	DRAWN REV L	DRAWN - PROG.
L1 gross incl. annex + bump-out	56,713		
L2 gross (rooms x 1.25 + loop)	28,186		
L1 + L2 gross	84,899		
Program footprint (max + annex + bump-out) vs L1	58,195	57,861	-334
PROGRAM TOTAL GSF vs drawn TOTAL	86,381	86,894	+513

The drum, the R = 20 ft envelope and the bay are circulation / building form, not program lines; the stair line (4 x 76 in, 31 risers, 12.67 x 24.08 ft each) is unchanged. Mech total about 4.1 % vs 5 % stays OPEN (D-072).

5 ROOMS THAT CHANGE (SF net of stairs)

LEVEL / ROOM	REV K / G	REV L / H	CHANGE
L1 15 MECH (N)	564	571	+7
L2 Stretch / Warm-up (N)	714	708	-6
L2 ST-2 landing / NE corner (not programmed)	141	142	+1
L1 + L2 ST-2 stair (20 ft tower -> 29 ft drum, each level)	314	660	+346

All other L1 / L2 rooms, tiers, seats (2,200) and the loop are unchanged (P2-A-101 Rev L / A-102 Rev H schedules).

6 EXITS / TRAVEL RECHECK FOR THE DRUM (P2-G-002 Rev E method)

- PASS (as calculated) Stair fit: 12.67 x 24.08 ft stair, diagonal 27.2 ft in about 27.7 ft inside: fits, 0.49 ft spare. Closes F1 of Rev E as geometry.
- PASS (as calculated) Stair capacity unchanged: 4 x 76 in = 304 in vs 292.0 in (Rev E); L2 load unchanged (loop and rooms the same).
- PASS (as calculated) X6 on the drum east face (196.5, 262.5): on the outline, outside the box, clear of annex and bay.
- PASS (as calculated) X5 / EXIT (N): bay at x 134 leaves a 12 ft lane between annex and bay (2.15 ft past the passage edge).
- PASS (as calculated) Stair separation: nearest pair ST-1 / ST-2 141 ft vs 1/3 diagonal 109 ft (Rev E: 136).
- PASS (as calculated) L2 travel, worst point (206, 140): about 160 ft incl. 15 ft seat access (Rev E: 162).

7 FINDINGS + OPTIONS (not redesigned here)

F1 Drum fit is tight: 0.49 ft total (about 3 in at each end corner) assumes about 8 in walls. Options: (a) keep 29 ft, architect confirms wall; (b) 30 ft drum, about +46 SF per level (rough); (c) stair turned / helical in the drum (IBC 1011 not checked).

F2 Drum door (SW face) is 4.6 ft from the loop edge along its swing line; landing at a 76 in stair door still needs the architect (Rev E F2, IBC 1010 not checked). Options: (a) door further west on the arc; (b) widen the strip at the drum.

F3 Drum to bay gap 3.5 ft (x 164 to 167.5): maintenance only, not an exit path. X6 discharges east.

F4 The approved Rev K / G base draws the east side of plan Rev I (bump-out y 161-217, X7 on its east face, no X11; phase2_plan_rev_i.yaml), not plan Rev J (D-072: bump-out y 119-175, public corridor, X7 on the wall, X11), which Set Rev D froze. Rev L keeps the approved base. Options: (a) rebase on plan Rev J in the next A-101 rev (areas unchanged); (b) record that Rev K's east side is intended.

F5 The old NE stair strip inside the box (x 185.9-210, y 246-252, about 71 SF on L1) is unassigned on Rev K and Rev L.

8 SOURCES

D-057, D-072, D-077..D-081 (DECISIONS_ARENA); ARENA P2-A-101_RevK / P2-A-102_RevG / P2-G-002_RevE (DXF read, regenerated identical); params/phase2_plan_rev_i.yaml, _rev_k, _rev_g_l2, _rev_l; P2-G-003 Rev K program lines. Revs A-K of P2-G-003 unchanged.

PRELIMINARY — CONCEPTUAL DESIGN — NOT FOR CONSTRUCTION

PROJECT	PHASE	SHEET TITLE	SCALE	DATE	REV	DRAWN BY	SHEET
Hazel Green Regional Athletic Complex Trojan Horse Arena · Hazel Green area, Madison County, Alabama (site TBD, D-006)	PHASE 2	PROGRAM + AREA STAIR DRUM · D-081 · D-057	NTS	October 2026	L	Drawn by KEYSTONE (AI) for Shane Brazelton	P2-G-003