

PROGRAM + AREA — REV N · P2-A-101 REV N / A-102 REV I · OLD NE STAIR STRIP = MECH (REMOTE), D-086

Program lines unchanged from P2-G-003 Rev K (frozen, Set Rev D). Drawn size (D-057) measured on P2-A-101 Rev N / A-102 Rev I. No SF cap (D-056). Planning only: architect confirms.

1 SIZE — D-057: L1 FOOTPRINT · L2 AREA · TOTAL GSF · CHANGE

	SET REV D	REV M / I	REV N / I	vs M / I	vs SET REV D
L1 FOOTPRINT	56,861	57,896	57,896	±0	+1,035
L2 AREA	28,933	29,068	29,068	±0	+135
TOTAL GSF	85,793	86,964	86,964	±0	+1,171

Drawn on: SET REV D = P2-G-003 Rev K (A-101 J / A-102 F); REV M / I = P2-G-003 Rev M (D-082..D-084); REV N / I = this sheet. Totals are the sum of the rounded levels.

GSF unchanged vs Rev M / I: the 67 SF strip was already inside the envelope; D-086 only names it.

2 HOW L1 AND L2 ARE MEASURED (Rev G method, D-079)

- Envelope = 210 x 252 ft box with R = 20 ft corners (D-077) united with the 30 ft drum at (182, 262.5): 53,216 SF.
- L1 = envelope + storage annex 2,100 + mech / elec bay 900 (x 134-164) + restroom bump-out 1,680 (y 119-175) = 57,896.
- L2 = envelope - open-to-below 24,148 (arena 132 x 168 + lobby 58 x 34) = 29,068.

3 PROGRAM (carried from P2-G-003 Rev K; no program line changes)

PROGRAM LINE (G-003 K)	SF	DRAWN REV N	DRAWN - PROG.
L1 gross incl. annex + bump-out	56,713		
L2 gross (rooms x 1.25 + loop)	28,186		
L1 + L2 gross	84,899		
Program footprint (max + annex + bump-out) vs L1	58,195	57,896	-299
PROGRAM TOTAL GSF vs drawn TOTAL	86,381	86,964	+583

The drum, the R = 20 ft envelope and the bay are circulation / building form, not program lines; the stair line (4 x 76 in, 31 risers, 12.67 x 24.08 ft each) is unchanged. Mechanical is not a separate program line (5 % of gross, R-014); see 5.

4 ROOMS THAT CHANGE vs REV M / I (SF net of stairs)

LEVEL / ROOM	REV M / I	REV N / I	CHANGE
L1 30 MECH (remote) (old NE stair strip)	0	67	+67

All other rooms on both levels unchanged (P2-A-101 Rev N, P2-A-102 Rev I).

5 MECHANICAL vs 5 % OF GSF (D-072 method, R-014)

TAG / ROOM	REV M	REV N	CHANGE
3 MECH / ELEC (NW)	931	931	±0
15 MECH (N)	564	564	±0
16 MECH (E)	675	675	±0
22 MECH (NE)	505	505	±0
28 MECH (E2)	660	660	±0
29 MECH / ELEC BAY	900	900	±0
30 MECH (remote)	0	67	+67
TOTAL MECHANICAL	4,234	4,302	+67
% of TOTAL GSF	4.87 %	4.95 %	+0.08

Target 5 % of 86,964 = 4,348 SF; 47 SF short. Set Rev D: 3,496 / 85,793 = 4.1 % (D-072). The rise since Set Rev D is mostly the 900 SF MECH / ELEC BAY (D-081). Planning check only; the MEP engineer sizes the rooms.

6 CARRIED FROM REV M (no change)

- Stair fit 1.49 ft spare in the 30 ft drum (D-082). Drum door at 235°, landing left for the architect (D-085).
- East side: T1 133 ft; common path 61 / 30 ft; corridor 96 in; dead end 5.2 ft (P2-G-003 Rev M).

7 FINDINGS + OPTIONS (not redesigned here)

F1 30 MECH (remote) does not touch the MECH / ELEC BAY (22.3 ft away) and has no door drawn. It shares 18.4 ft of wall with MECH (NE) 22 and 2.0 ft with MECH (N) 15. Options: (a) reach it through MECH (NE) 22; (b) merge it into 22; (c) MEP engineer decides. It is about 6 ft deep, so equipment fit is TBD.

F2 Mechanical 4.95 % vs 5 % (47 SF short); MEP OPEN (D-072).

F3 Drum door landing reaches 4.9 in onto the Level 2 loop: left for the architect (D-085). X7 / X11 discharge TBD (D-006).

8 SOURCES

D-057, D-072, D-077..D-086 (DECISIONS_ARENA); R-014; params/phase2_plan_rev_j.yaml (= Set Rev D A-101 J), _rev_k, _rev_g_l2, _rev_m, _rev_n; phase2_life_safety_rev_d.yaml / phase2_code_rev_d.yaml (handoff, read only); IBC 2021 1010.1.5, T1017.2, T1006.2.1, 1020.5, T1020.3. Revs A-M of P2-G-003 unchanged.

PRELIMINARY — CONCEPTUAL DESIGN — NOT FOR CONSTRUCTION

PROJECT	PHASE	SHEET TITLE	SCALE	DATE	REV	DRAWN BY	SHEET
Hazel Green Regional Athletic Complex Trojan Horse Arena · Hazel Green area, Madison County, Alabama (site TBD, D-006)	PHASE 2	PROGRAM + AREA MECHANICAL · D-086	NTS	October 2026	N	Drawn by KEYSTONE (AI) for Shane Brazelton	P2-G-003