

HAZEL GREEN REGIONAL ATHLETIC COMPLEX

PHASE 1 — REMODEL OF EXISTING WRESTLING ROOM

Requested by: Shane Brazelton — 256-508-4608 / brazeltonshane@gmail.com

Location: Hazel Green, Madison County, Alabama
Rooms: existing wrestling room + adjacent walk-through room
For review by: principal + district facilities

WHAT THIS PROJECT DOES — 3 WORK ITEMS

W1 — WALL PADDING

Proper training wall pads on the wrestling room walls. Finish work, not new construction.

Why: Wrestlers can get hurt when they are thrown or fall into bare, unpadded walls during practice. Proper wall pads lower that risk.

Walls to pad: TBD

Pad height: 6 ft

Pad thickness: TBD

Who buys or donates: TBD (school purchase, donation, or fundraiser)

Door hardware: Recess from wall surface where possible. Walls flat, no bump-outs.

FIRE SAFETY — BEFORE BUYING PADS

Wall pads must have an NFPA 286 assembly test report — not a foam-only rating. Ask the vendor before purchase.

Code basis: 2021 IBC 806.2 and 803.4 → 2603.9 (Alabama Building Code).

W2 — PLUMBING REPAIR

Repair plumbing already failing in the existing building.

Why: Failing plumbing is getting worse the longer it waits.

Where: TBD

Problem spots: TBD

Existing fixtures: TBD

Water / drain lines: TBD / TBD

WHO DESIGNS IT

BY LICENSED PLUMBER / ENGINEER OF RECORD

This package gives: scope narrative + fixture list only (no plumbing design).
Plumbing code: 2021 IPC (Alabama).

W3 — RESTROOM SPLIT

Why: The route to the training room is an open walk-through room.

Result: 1 male + 1 female athlete restroom (single-user, one per sex).

Accessibility: full 2010 ADA Standards, BOTH rooms.

Where / room sizes: TBD — waiting on measurements.

KEY 2010 ADA NUMBERS FOR EACH RESTROOM

Item	Requirement	2010 ADA §
Turning space	60 in circle (or T-shape)	304.3
Clear space at toilet	60 in wide × 56 in deep, min	604.3.1
Toilet centerline to side wall	16–18 in	604.2
Toilet seat height	17–19 in	604.4
Side grab bar	42 in long min; starts ≤ 12 in from rear wall	604.5.1
Rear grab bar	36 in long min	604.5.2
Grab bar height (top)	33–36 in	609.4
Sink clear floor space	30 × 48 in, forward	305.3, 606.2
Sink rim height	34 in max	606.3
Mirror bottom edge	40 in max above floor	603.3
Door clear width	32 in min	404.2.3
Door handle height	34–48 in	404.2.7
Door swing	not over toilet/sink clear space unless a 30 × 48 in space is beyond the swing	603.2.3
Room sign	tactile, 48–60 in high, latch side	703.4

Planning numbers only. The final restroom layout comes after the rooms are measured.

NOT INCLUDED

- × The Phase 2 new building complex (55,000 SF)
- × Stadium seats
- × Any new structure

Phase 1 is a remodel of existing rooms only.

WHO APPROVES

1. Principal
2. District facilities (MCSS Operations & Facilities)
3. Others as the district requires


District guidelines send campus building improvements to the Board of Education. State building review (Alabama DCM) may also apply.

Scope confirmation expected: ~end of October 2026 (principal + facilities)


WHAT WE'RE ASKING THE SCHOOL FOR

1. Permission to measure and photograph the wrestling room and walk-through room
2. A district facilities contact
3. How approval works for this kind of work

PHOTOS



PHOTOS TBD



PHOTOS TBD

Wrestling room

Walk-through room

PRELIMINARY — CONCEPTUAL DESIGN — NOT FOR CONSTRUCTION

PROJECT	PHASE	SHEET TITLE	SCALE	DATE	REV	DRAWN BY	SHEET
Hazel Green Regional Athletic Complex Hazel Green, Madison County, Alabama	PHASE 1 REMODEL	SCOPE SHEET PHASE 1 — REMODEL OF EXISTING WRESTLING ROOM	NTS	October 2026	B	Drawn by KEYSTONE (AI) for Shane Brazelton	P1-G-001