

Trojan Horse Arena — Phase 2 Schematic Set Rev D + Cost Estimate (R-025 Rev B)

Hazel Green Regional Athletic Complex · Hazel Green, Madison County, Alabama (site TBD) · prepared for Shane Brazelton · October 4, 2026

PRELIMINARY — CONCEPTUAL DESIGN — NOT FOR CONSTRUCTION · NOT A BID · drawn by AI (KEYSTONE / Claude)

THE BUILDING, AS DRAWN

- **85,793 GSF** on two levels (L1 56,861 + L2 28,933): 210 × 252 ft + NE stair tower + 2,100 SF chair / table / stage storage annex + 1,680 SF restroom bump-out. No square-foot cap; size is set by budget and parcel.
- **Event floor 120 × 144 ft**, four 42-ft wrestling mats. **2,200 seats**: 1,100 telescopic lower + 1,100 fixed upper. Uses: sports plus chairs-only events (graduations, banquets, expos). No standing-concert design.
- **Entry and exits**: one controlled public entry (8-pair door bank, 512 in), 4 exit stairs at 76 in, screening in a lobby side bay. Restrooms sized to the chairs-only load: 22 men's / 42 women's WC. Core 2 sits on the east wall, reached by an 8 ft public corridor from the east concourse; EXIT (E) stays clear; new exit X11.
- **Brand pieces**: freestanding limestone portal (≤ 50 ft, arch crown 34 ft, crimson underside, gold trim, 11 ft badge) over a 28 ft brick Champion Walk that widens to 40 ft at the doors.
- **Alabama requires a registered architect** for this building. This set is the program package for that architect; code basis IBC 2021 is assumed and the AHJ must confirm.

THE SET — APPROVED AND FROZEN (D-073)

Phase2_Schematic_Set_RevD.pdf, 13 sheets: G-001 cover · G-002 code analysis · G-003 program test-fit · C-101 site plan · A-101 / A-102 floor plans L1 / L2 · A-103 floor overlays (mats, seating, conversions) · A-111 life safety · A-201 elevations · A-301 sections · A-302 sight lines · A-401 enlarged plans (locker rooms, restroom core 2) · A-901 3D massing. New revisions are new files; older revisions are kept.

COST ESTIMATE — R-025 REV B (ROUGH ORDER OF MAGNITUDE, GOOD TO ABOUT -25% / +50%)

ROM COST (2026 \$, excl. land)	Low	Mid	High
Building, 85,793 GSF (\$215 / \$260 / \$340 per SF)	\$18.4M	\$22.3M	\$29.2M
Seating + event equipment	\$0.6M	\$1.1M	\$2.1M
Grand Entrance Portal Champion Walk	\$0.57M \$0.10M	\$1.05M \$0.13M	\$1.80M \$0.17M
Parking (734 spaces, assumed) + other site work	\$4.2M	\$5.9M	\$8.5M
Design / permit / testing fees + contingency	\$3.2M	\$6.8M	\$13.0M
TOTAL PROJECT	\$27.1M	\$37.3M	\$54.7M
All-in per GSF	\$316	\$435	\$638

- **Working planning number: \$39M** (mid; range \$28–57M; excluding land) — **planning only, not a budget target** (D-012 stays open). Rev B's mid is \$37.3M after removing a double-counted architect fee (the RSMeans base already includes 7% A/E and 25% contractor fees); \$39M stays as the conservative working figure.
- **Parking sensitivity** (mid total): 100% of 734 spaces \$37.3M · 50% \$34.7M · 25% \$33.3M — but only if the missing spaces are truly supplied elsewhere.
- **Portal**: the high case may exceed \$1.8M (about +\$1.1M on the high total in one illustration) until a structural engineer sizes the freestanding arch.
- **Not included**: land, financing, utility and impact fees, off-site work, escalation (about 5% a year), owner sales tax. Possible gap: GC overhead / profit on seating, portal, parking and site lines (up to about \$2.1M at mid).
- **Confidence is low-to-medium**. Building \$/SF comes from RSMeans (2019 gym model, escalated with the Turner index and adjusted to Huntsville) and 2026 published ranges; seating, portal, equipment, fees and contingency are allowances. **A general contractor or estimator should price the set before any lender or donor use.**

WHAT IS STILL OPEN

- **Shane's decisions**: parcel (D-006) · owner of record (D-007) · AHJ pre-application with Madison County and code edition (D-008) · budget target (D-012) · trademark search (D-042) · donor-brick program and pricing (D-044) · locker parity, concessions scope.
- **Architect / engineers**: upper-tier structure depth ≤ 1'-6" (7'-6" clear under the upper tier, zero margin) · portal structure · restroom plumbing and mechanical space (total mech about 4.1% vs 5% planning; the annex can absorb about 800 SF) · door widths, construction type, allowable area · exit discharge to a public way.

Sources: Phase2_Schematic_Set_RevD.pdf (sheet G-001 index), DECISIONS_ARENA D-070 to D-073, R-025 Rev B (RSMeans gymnasium model, Turner Building Cost Index, RSMeans city cost index, 2026 contractor cost guides). Everything here is preliminary and every assumption is labeled on the sheets and in R-025.