

HAZEL GREEN REGIONAL ATHLETIC COMPLEX

PHASE 1 — REMODEL OF EXISTING WRESTLING ROOM

Requested by: Shane Brazelton — 256-508-4608 / brazeltonshane@gmail.com

Location: Hazel Green, Madison County, Alabama
Rooms: existing wrestling room + adjacent walk-through room
For review by: principal + district facilities

WHAT THIS PROJECT DOES — 3 WORK ITEMS, IN PRIORITY ORDER

W2 — RESTORE WATER / PLUMBING REPAIR PRIORITY 1 No running water to the area. All fixtures out of service. Cause unknown. Restore running water to the area and repair the plumbing so the fixtures work again. Why: Athletes have no working restroom or handwashing during practice; hygiene matters in a contact sport. Where: TBD Problem spots: TBD Existing fixtures: TBD Water / drain lines: TBD / TBD WHO DESIGNS IT BY LICENSED PLUMBER / ENGINEER OF RECORD This package gives: scope narrative + fixture list only (no plumbing design). Plumbing code: 2021 IPC (Alabama).	W3 — RESTROOM SPLIT PRIORITY 2 Why: The route to the training room is an open walk-through room. Result: 1 male + 1 female athlete restroom (single-user, one per sex). Accessibility: full 2010 ADA Standards, BOTH rooms. Where / room sizes: TBD — waiting on measurements. KEY 2010 ADA NUMBERS FOR EACH RESTROOM <table><tr><th>Item</th><th>Requirement</th><th>2010 ADA §</th></tr><tr><td>Turning space</td><td>60 in circle (or T-shape)</td><td>304.3</td></tr><tr><td>Clear space at toilet</td><td>60 in wide × 56 in deep, min</td><td>604.3.1</td></tr><tr><td>Toilet centerline to side wall</td><td>16–18 in</td><td>604.2</td></tr><tr><td>Toilet seat height</td><td>17–19 in</td><td>604.4</td></tr><tr><td>Side grab bar</td><td>42 in long min; starts ≤ 12 in from rear wall</td><td>604.5.1</td></tr><tr><td>Rear grab bar</td><td>36 in long min</td><td>604.5.2</td></tr><tr><td>Grab bar height (top)</td><td>33–36 in</td><td>609.4</td></tr><tr><td>Sink clear floor space</td><td>30 × 48 in, forward</td><td>305.3, 606.2</td></tr><tr><td>Sink rim height</td><td>34 in max</td><td>606.3</td></tr><tr><td>Mirror bottom edge</td><td>40 in max above floor</td><td>603.3</td></tr><tr><td>Door clear width</td><td>32 in min</td><td>404.2.3</td></tr><tr><td>Door handle height</td><td>34–48 in</td><td>404.2.7</td></tr><tr><td>Door swing</td><td>not over toilet/sink clear space unless a 30 × 48 in space is beyond the swing</td><td>603.2.3</td></tr><tr><td>Room sign</td><td>tactile, 48–60 in high, latch side</td><td>703.4</td></tr></table> Planning numbers only. The final restroom layout comes after the rooms are measured.	Item	Requirement	2010 ADA §	Turning space	60 in circle (or T-shape)	304.3	Clear space at toilet	60 in wide × 56 in deep, min	604.3.1	Toilet centerline to side wall	16–18 in	604.2	Toilet seat height	17–19 in	604.4	Side grab bar	42 in long min; starts ≤ 12 in from rear wall	604.5.1	Rear grab bar	36 in long min	604.5.2	Grab bar height (top)	33–36 in	609.4	Sink clear floor space	30 × 48 in, forward	305.3, 606.2	Sink rim height	34 in max	606.3	Mirror bottom edge	40 in max above floor	603.3	Door clear width	32 in min	404.2.3	Door handle height	34–48 in	404.2.7	Door swing	not over toilet/sink clear space unless a 30 × 48 in space is beyond the swing	603.2.3	Room sign	tactile, 48–60 in high, latch side	703.4	W1 — WALL PADDING PRIORITY 3 — CAN RUN IN PARALLEL Does not depend on water. Proper training wall pads on the wrestling room walls. Finish work, not new construction. Why: Wrestlers can get hurt when they are thrown or fall into bare, unpadded walls during practice. Proper wall pads lower that risk. Walls to pad: TBD Pad height: 6 ft Pad thickness: TBD Who buys or donates: TBD (school purchase, donation, or fundraiser) Door hardware: Recess from wall surface where possible. Walls flat, no bump-outs. FIRE SAFETY — BEFORE BUYING PADS Wall pads must have an NFPA 286 assembly test report — not a foam-only rating. Ask the vendor before purchase. Code basis: 2021 IBC 806.2 and 803.4 → 2603.9 (Alabama Building Code).
Item	Requirement	2010 ADA §																																													
Turning space	60 in circle (or T-shape)	304.3																																													
Clear space at toilet	60 in wide × 56 in deep, min	604.3.1																																													
Toilet centerline to side wall	16–18 in	604.2																																													
Toilet seat height	17–19 in	604.4																																													
Side grab bar	42 in long min; starts ≤ 12 in from rear wall	604.5.1																																													
Rear grab bar	36 in long min	604.5.2																																													
Grab bar height (top)	33–36 in	609.4																																													
Sink clear floor space	30 × 48 in, forward	305.3, 606.2																																													
Sink rim height	34 in max	606.3																																													
Mirror bottom edge	40 in max above floor	603.3																																													
Door clear width	32 in min	404.2.3																																													
Door handle height	34–48 in	404.2.7																																													
Door swing	not over toilet/sink clear space unless a 30 × 48 in space is beyond the swing	603.2.3																																													
Room sign	tactile, 48–60 in high, latch side	703.4																																													

NOT INCLUDED × The Phase 2 new building complex (55,000 SF) × Stadium seats × Any new structure Phase 1 is a remodel of existing rooms only.	WHO APPROVES 1. Principal 2. District facilities (MCSS Operations & Facilities) 3. Others as the district requires District guidelines send campus building improvements to the Board of Education. State building review (Alabama DCM) may also apply. Scope confirmation expected: ~end of October 2026 (principal + facilities)	WHAT WE'RE ASKING THE SCHOOL FOR 1. Permission to measure and photograph the wrestling room and walk-through room 2. A district facilities contact 3. How approval works for this kind of work 4. A plumber visit to diagnose why there is no water (shutoff, supply line, or other)	PHOTOS PHOTOS TBD Wrestling room PHOTOS TBD Walk-through room
---	--	---	--

PRELIMINARY — CONCEPTUAL DESIGN — NOT FOR CONSTRUCTION

PROJECT	PHASE	SHEET TITLE	SCALE	DATE	REV	DRAWN BY	SHEET
Hazel Green Regional Athletic Complex Hazel Green, Madison County, Alabama	PHASE 1 REMODEL	SCOPE SHEET PHASE 1 — REMODEL OF EXISTING WRESTLING ROOM	NTS	October 2026	C	Drawn by KEYSTONE (AI) for Shane Brazelton	P1-G-001