



TROJAN HORSE ARENA

Hazel Green Regional Athletic Complex

Hazel Green area, Madison County, Alabama (site TBD, D-006)

PHASE 2 — SCHEMATIC DESIGN SET · REV B

Program package for the Alabama-registered architect of record · October 2026

PROJECT

Building	Indoor athletic arena, 2 levels; 210 x 252 ft + NE stair tower, + storage annex (north) + restroom bump-out (east)
Owner / client	Shane Brazelton (owner of record OPEN, D-007)
Site	TBD — unincorporated Hazel Green, Madison County, AL (D-006)
Code basis	IBC 2021 ASSUMED; county on 2018, State Fire Marshal on 2021 — AHJ to confirm (D-008)
Occupancy	A-4 main (arena), nonseparated mixed, fully sprinklered (ASSUMED, P2-G-002)
Construction type	TBD (architect)

GENERAL NOTES

- PRELIMINARY — CONCEPTUAL DESIGN — NOT FOR CONSTRUCTION. Schematic program package only; not a code review, not sealed.
- Alabama requires a registered architect for this assembly building (Ala. Admin. Code 100-X-4-.03). This set is the program for that architect, who sets door widths, construction type, structure and MEP.
- Labels on every sheet: DECIDED = Shane's decision (D-####); ASSUMED = KEYSTONE / Claude placeholder; CITED = code or source reference.
- Drawn by AI (KEYSTONE / Claude) for Shane Brazelton. Older revisions are frozen history; new revisions are new files.

SHEET INDEX — PHASE 2 SCHEMATIC SET REV B (sheet-number order)

SHEET	TITLE	REV	STATUS
P2-G-001	Cover sheet — sheet index + decisions	A	NEW (this sheet)
P2-G-002	Code analysis (schematic)	C	IN REVIEW (last approved Rev A)
P2-G-003	Program test-fit — program + loop + storage + restrooms	K	IN REVIEW (last approved Rev H)
P2-C-101	Site plan — campus diagram (site TBD)	E	IN REVIEW (no rev approved yet)
P2-A-101	Overall floor plan — Level 1 (block plan)	I	IN REVIEW (last approved Rev D)
P2-A-102	Overall floor plan — Level 2 (block plan)	F	IN REVIEW (last approved Rev D)
P2-A-103	Floor overlays — mats, seating + conversions	B	IN REVIEW (last approved Rev A)
P2-A-111	Life safety plan — Levels 1 + 2	C	IN REVIEW (last approved Rev A)
P2-A-201	Exterior elevations	H	IN REVIEW (last approved Rev F)
P2-A-301	Building sections	D	IN REVIEW (no rev approved yet)
P2-A-302	Sight-line study	C	IN REVIEW (no rev approved yet)
P2-A-401	Enlarged plans — locker rooms + restroom core 2	C	IN REVIEW (last approved Rev A)
P2-A-901	3D massing model — views	C	IN REVIEW (no rev approved yet)

IN REVIEW = drawn after Shane's decisions, awaiting his sign-off. Phase 2 Schematic Set Rev A (G-003 F, A-101 D, A-102 D; D-036) stays frozen. P2-A-103 Rev B predates D-069: the floor chair layouts still need an aisle kept open to V2 (next A-103 rev).

SIZE — D-057 (drawn, R-021 method; no SF cap, D-056)

	SET REV B	REV H	CHANGE	SET REV A	CHANGE
Level 1 footprint	56,861	55,181	+1,680	51,503	+5,358
Level 2 area	28,933	28,933	0	28,363	+570
TOTAL GSF	85,793	84,113	+1,680	79,866	+5,927

Rev H = plan before the D-069 bump-out (+1,680 SF, L1 only). Set Rev A = plan Rev D (frozen baseline, D-036). Program total on P2-G-003 Rev K: 86,381 GSF (drawn – program = –588).

KEY FACTS (as drawn)

- Event floor 120 x 144 ft drawn (16,400 SF program, D-030); 4 x 42 ft mats, 2 x 2 (D-014).
- 2,200 seats = 1,100 telescopic lower + 1,100 fixed upper; upper tier steps down from the L2 loop, 21 in risers (D-009, D-049, D-061); east seats 16 ft from the mats (D-053).
- Level 2 FF 17'-9" (D-061); 2-lane running / training loop (D-035, D-037); roofs: ring 32.75 ft, arena 42 ft, structure underside 36 ft (ASSUMED).
- Exits: E1 main = 8-pair door bank, 512 in clear, single controlled entry (D-033, Option 1 11:07 AM CT); 4 stairs x 76 in, 31 risers (D-051, D-052). 7'-6" clear under the upper-tier front, zero margin (structure ≤ 1'-6" ASSUMED).
- Restrooms (chairs-only case, load 3,446): lobby core + core 2 = 22 men's / 42 women's WC, 9 / 12 lav, 4 DF (D-064, D-069, D-070).
- Event lockers 4 x 900 = 3,600 SF (D-060); chair / table / stage storage annex 2,100 SF on the north wall with S1 (D-067).

DECISIONS SUMMARY (DECIDED — Shane; full log: DECISIONS.md)

D-###	DECISION
D-030	Two-level program around a 16,400 SF event floor; 2,200 seats (with D-009, D-032).
D-033	Single controlled public entry at E1; E1 = 8-pair door bank (Option 1, 11:07 AM CT).
D-034	Deliveries at north door S1 (staff only); bus loop south, offset from the portal view.
D-035/037	Continuous Level 2 running / training loop, 2 lanes x 42 in.
D-039	SW flex / storage and team assembly kept as drawn.
D-041	Official mark = Shane's circular horse-head badge; red #CC0000 / black.
D-043/050	Grand Entrance Portal freestanding over the Champion Walk; ≤ 50 ft, arch crown 34 ft (structural engineer required).
D-045/047	Portal arch underside crimson, gold trim; badge 11 ft dia + 27 in wordmark.
D-046/066	Champion Walk 28 ft brick, widened to 40 ft at the doors (6 ft paved bands); 4x8 / 8x8 donor bricks.
D-049/053/061	Upper tier steps down from the L2 loop; east seats 16 ft from mats; L2 FF 17'-9", 21 in risers.
D-051/052	4 exit stairs x 76 in clear, intermediate handrails; landing ≥ stair width.
D-054	Floor uses: sports + chairs-only events (graduations, banquets, expos). No standing-concert design.
D-056/057	No SF cap — size set by budget + parcel; every area table shows L1, L2, total, change.
D-060	Event lockers back to full 3,600 SF behind the tier.
D-064	L1 restrooms sized to the chairs-only case; posted loads per configuration; temp units beyond.
D-065	Security screening in a side bay of the lobby, off the egress path.
D-067	Chair / table / stage storage (~2,350 chairs + tables + stage) near the floor and S1.
D-069/070	Second restroom pair (core 2) in a one-storey 30 x 56 ft bump-out on the EAST wall at V2.

OPEN — OWNER / ARCHITECT / ENGINEER

- D-006: Site / parcel (drives X7 discharge, bus loop, utilities, site work)
 - D-007: Owner of record
 - D-008: Code edition + AHJ pre-application (Madison County)
 - D-012: Phase 2 budget target (ROM estimate in progress)
 - D-042: Trademark search before signage / apparel
 - D-044: Donor-brick program + pricing
 - D-010/011/013: Locker parity, concessions scope, girls 3,503 SF tag
 - Structural: Upper-tier structure depth ≤ 1'-6" (7'-6" clear, zero margin); portal + arch
 - MEP: Core-2 plumbing routing and 16 ft bump-out height (ASSUMED)
 - Architect: Door widths + hardware, construction type, allowable area, smoke-protected seating
- Red = owner decisions (Shane). Others go to the architect of record / engineers.

PRELIMINARY — CONCEPTUAL DESIGN — NOT FOR CONSTRUCTION

PROJECT	PHASE	SHEET TITLE	SCALE	DATE	REV	DRAWN BY	SHEET
Hazel Green Regional Athletic Complex Trojan Horse Arena · Hazel Green area, Madison County, Alabama (site TBD, D-006)	PHASE 2	COVER SHEET SHEET INDEX + DECISIONS	NTS	October 2026	A	Drawn by Claude (AI) for Shane Brazelton	P2-G-001